

Installation manual Front leveling kit 2014-2016 Ram 2500 4WD 2013 - 2016 Ram 3500 4WD Part # 32909

sj10182013rev.02

Part # 32909 Important customer information: 2014-2016 Ram 2500 4WD 2013 - 2016 Ram 3500 4WD Tuff Country EZ-Ride Suspension highly recommends Front leveling kit that a qualified or a certified mechanic performs this installation. **Description** <u>Qty.</u> <u>Part #</u> 32909-01 Front coil spring spacer 2 It is the responsibility of the customer/installer to wear 2 14056-02 Front shock relocation bracket safety glasses at all times when performing this instal-1 32909NB Hardware bag lation. 32909INST 1 Instruction manual MIRRORHANGER Rear view mirror hanger 1 It is the customers/installers responsibility to read and 1 WARNINGDECAL Warning decal understand all steps before installation begins. If you INSTFILLER Instruction filler 1 have any questions or concerns, please contact our NAMETAG Name tag technical department @ (801) 280-2777. Also, the OEM manual should be used as a reference guide. Congratulations on your selection to purchase a Tuff This vehicles reaction and handling characteristics Country EZ-Ride Suspension System. We at Tuff may differ from standard cars and/or trucks. Country EZ-Ride Suspension are proud to offer a high Modifications to improve and/or enhance off road perquality product at the industries most competitive pricformance may raise the intended center of gravity. ing. Thank you for your confidence in us and our prod-Extreme caution must be utilized when encountering uct. driving conditions which may cause vehicle imbalance or loss of control. DRIVE SAFELY! Avoid abrupt If you desire to return your vehicle to stock, it is the maneuvers: such as sudden sharp turns which could customers responsibility to save all stock hardware cause a roll over, resulting in serious injury or death. and components. It is the customers responsibility to make sure that a The Tuff Country EZ-Ride Suspension product safety re-torque is performed on all hardware associated with label that is included in your kit box must be installed this suspension system after the first 100 miles of inside the cab in plain view of all occupants. installation. It is also the customers responsibility to do a complete re-torque after every 3000 miles or after every off road use. After the original installation, Tuff Country EZ-Ride Suspension also recommends having the alignment checked every 6 months to ensure proper tracking, proper wear on tires and front end components. Tuff Country EZ-Ride Suspension takes no responsibility for abuse, improper installation or improper suspension maintenance.

Limited lifetime warranty	Important information that needs to be read before installation begins:
Notice to all Tuff Country EZ-Ride Suspension customers: It is your responsibility to keep your original sales receipt! If failure should occur on any Tuff Country EZ-Ride Suspension component, your original sales receipt must accompany the warranted unit to receive warranty. Warranty will be void if the customer can not provide the original sales receipt. Do not install a body lift in conjunction with a suspension system. If a body lift is used in conjunction with any	This leveling kit is designed to fit the new style 3 link front suspension. You can identify this by your front shock being outside the front coil spring. If your front shock is inside the coil spring, you will need to order part # 32900 Tuff Country recommends a 35" x 12.50" tire and wheel package. If taller than a 35" tire is installed, Tuff Country
Tuff Country EZ-Ride Suspension product, your Tuff Country EZ-Ride Suspension WARRANTY WILL BE VOID. Tuff Country Inc. ("Tuff Country") suspension products are warranted to be free from defects in material and workmanship for life if purchased, installed and maintained on a non-commercial vehicle; otherwise, for a period of twelve (12) months, from the date of purchase and installation on a commercial	assumes no liability and the warranty will be VOID! This leveling kit comes with front shock relocation brackets to be used with the OE shocks. If after market front shocks are wanted, Tuff Country EZ Ride Suspension recommends installing a 23" fully extended front shock without the front shock relocation bracket.
vehicle, or twelve thousand (12,000) miles (which ever occurs first). Tuff Country does not warrant or make any representations concerning Tuff Country Products when not installed and used strictly in accordance with the manufacturer's instructions for such installation and operation and accordance with good installation and maintenance practices of the automotive industry. This warranty does not apply to the cosmetic finish of Tuff Country products nor to	This Leveling kit comes with (1) installation manual and some post installation procedure literature and it is the installers responsibility to make sure that the customer receives the post installation procedure literature. If a customer would like a copy of the installation manual, please have them visit our website at www.tuffcoun- try.com. Have them go to the customer care section to download these instructions. If you have any questions, please feel free to call us at (801) 280-2777.
Tuff Country products which have been altered, improperly installed, maintained, used or repaired, or damaged by accident, negligence, misuse or racing. ("Racing is used in its broadest sense, and, for example, without regards to formalities in relation to prizes, competition, etc.) This warranty is void if the product is removed from the original vehicle and re-installed on that or any other vehicle. This warranty is exclusive and is in lieu of any implied warranty of merchantability, fitness for a particular purpose or other warranty of quality, whether express or implied,	Before installation begins, Tuff Country EZ-Ride Suspension highly recommends that the installer performs a test drive on the vehicle. During the test drive, check to see if there are any uncommon sounds or vibrations. If uncommon sounds or vibrations occur on the test drive, uncommon sounds or vibrations will be enhanced once the suspension system has been installed. Tuff Country EZ-Ride Suspension highly recommends notifying the customer prior to installation to inform the customer of these issues if they exist.
except the warranty of title. All implied warranties are limited to the duration of this warranty. The remedies set forth in this warranty are exclusive. This warranty excludes all labor charges or other incidental of consequential damages. Any part or product returned for warranty claim must be returned through the dealer of the distributor from whom it was purchased.	Make sure to use loctite on all new and stock hardware associated with the installation of this suspension sys- tem. Special note: Before installation begins, it is the customers/installers responsibility to make sure that all parts are on hand. If any parts are missing, please feel
Tuff Country reserves the right to examine all parts returned to it for warranty claim to determine whether or not any such part has failed because of defect in material or workmanship. The obligation of Tuff Country under this warranty shall be limited to	free to call one of our customer service representatives @ (801) 280-2777. Recommended tools selection:
repairing, replacing or crediting, at its option, any part or product found to be so defective. Regardless of whether any part is repaired, replaced or credited under this warranty, shipping and/or transportation charges on the return of such product must be prepaid by the customer under this warranty.	Torque wrench Standard socket set Standard wrench set Metric socket set Metric wrench set Tape measure Hydraulic floor jacks

4. Working on the driver side, remove the sway bar end link Hardware bag 32909NB includes: from the sway bar. Save the hardware. Repeat procedure on the passenger side. **Description** Quantity 9163B (9/16" x 3" bolt) 2 12WA (1/2" USS flat washer) 4 2 916UN (9/16" unitorque nut) 381B (3/8" x 1" bolt) 2 516WA (5/16" USS flat washer) 4 38UN (3/8" unitorque nut) 2 Please follow instructions carefully: Before installation begins, measure from the center of the hub, to the bottom of the fender well, and record measurements below. Pre-installation measurements: 5. Carefully lower down on both hydraulic floor jacks at the same time allowing enough room for the new coil spring spacer to be installed. Special note: Take special care not Driver side front: over extend any brake lines or hoses. Passenger side front: At the end of the installation take the same 6. Working on the driver side, remove the coil spring from the measurements and compare to the pre-installation vehicle and set aside. Repeat procedure on the passenger side. measurements. Post-installation measurements: Driver side front: Passenger side front: Front end installation: 1. To begin installation, block the rear tires of the vehicle so that the vehicle is stable and can't roll backwards. Safely lift the front of the vehicle and support the vehicle with a pair of jack stands. Place a jack stand on both the driver and the passenger side. Next, remove the front wheels and tires from both sides. Place a pair of hydraulic floor jacks under the front axle. Place one on the driver side and passenger side. Carefully raise up on both hydraulic floor jacks at the same time until 7. Working on the driver side, remove the coil spring isolator from the upper coil spring pocket and set aside. Repeat prothey come into contact with the front axle. cedure on the passenger side. 3. Working on the driver side, remove the shock from the vehicle and save the upper and lower hardware. Repeat procedure on the passenger side.

8. Locate the new coil spring spacers. Also, locate (2) 3/8" x 10. Locate the new front shock relocation brackets. Locate 1" bolt, (4) 5/16" USS flat washers and (2) 3/8" unitorque (2) 9/16" x 3" bolt, (4) 1/2" USS flat washers and (2) 9/16" unitorque nuts from hardware bag 32909NB. Working on the driver unitorque nuts from hardware bag 32909NB. Install the new side, install the new coil spring spacer to the upper coil shock relocation brackets to the bottom of the stock shocks spring pocket and secure using the new 3/8" hardware. **Special note: The hole is already provided in the upper**


coil spring pocket. Also, make sure to use loctite and torque the 3/8" hardware to 28 ft lbs. Repeat procedure on the driver side, install the modified shock into the passenger side.



9. Locate the OE upper coil spring isolator and coil springs. Working on the driver side, install the isolator to the top of the coil spring and install the coil spring back into the vehicle. Carefully raise up on the hydraulic floor jack until the coil spring and isolator seat properly into the newly installed coil spring spacer. Repeat procedure on the passenger side.



11. Working on the driver side, install the modified shock into the upper and lower location using the OE hardware. Make sure to use loctite and torque the lower mounting hardware to **85 ft lbs.** and the upper mounting hardware to **22 ft lbs.** Move back to the new 9/16" hardware and add some loctite and torque to **85 ft lbs.** Repeat procedure on the passenger side.



12. Working on the driver side, install the sway bar back to the sway bar end link and secure using the OE hardware. Make sure to use loctite and torque to **40 ft lbs.** Repeat procedure on the passenger side.



13. Carefully remove the (2) hydraulic floor jacks from under the front axle.

14. Install the tires and wheels and carefully lower the vehicle to the ground.

Congratulations, installation complete!

Special note: After the completion of the installation, Tuff Country EZ-Ride Suspension recommends taking the vehicle to an alignment shop and having a proper front end alignment performed.

Tuff Country EZ-Ride Suspension recommends that a complete re-torque is done on all bolts associated with this suspension system. It is the customers responsibility to make sure that a re-torque is performed on all hardware associated with this suspension system after the first 100 miles of installation. It is also the customers responsibility to do a complete re-torque after every 3000 miles or after every off road use. Neglect of following these steps could cause brackets to come loose and cause serious damage to the suspension system and to the vehicle.

This Suspension System comes with (1) installation manual and some post installation procedure literature and it is the installers responsibility to make sure that the customer receives the post installation procedure literature. If a customer would like a copy of the installation manual, please have them visit our website at www.tuffcountry.com. Have them go to the customer care section to download these instructions. If you have any questions, please feel free to call us at (801) 280-2777.

If you have any questions or concerns, please feel free to contact Tuff Country or your local Tuff Country dealer.